CLEMSON
FACILITIES

NOTICE OF CONSTRUCTION DISRUPTION

Details

Facility Affected: MARTIN HALL E-SECTION

Location(s): MULTIPLE LEVELS - SEE DETAILS IN DESCRIPTION

START Date / Time: 11/26/2012 7:00 AM **END Date / Time:** 1/04/2013 6:00 PM

Disruption Description

There will be a pipe restoration project beginning in MARTIN HALL E-SECTION on MONDAY, NOVEMBER 26, 2012 7:00 AM through FRIDAY, JANUARY 4, 2013 6:00 PM. Curaflo will be cleaning and applying an epoxy lining to the hot/chilled water system within building in order to extend the life of the pipe system. There will be approximately 4 contractor vehicles parked adjacent to Martin Hall along with air compressors, hoses and other equipment as needed. This may cause temporary blockage of egress in and out of the building at the ground floor entrance on the east end of the building (closest to Long Hall).

Contractors will be working with equipment and hoses in all areas of the building including stairwells, offices, corridors and restrooms. The planned schedule is as follows:

PHASE 1: The contractors will be primarily on 2nd and 3rd floors including stairwells and restrooms beginning November 26, 2012 through December 3, 2012.

PHASE 2: The contractors will be primarily on 1st and 2nd floors including stairwells and restrooms beginning December 4, 2012 through December 11, 2012.

PHASE 3: The contractors will be primarily on Ground Floor and restrooms beginning December 12, 2012 through January 4, 2013.

As part of this project, asbestos abatement may be required in some areas. This has not been confirmed at the time of this notice. In the event abatement is required, certified personnel will conduct the abatement after normal working hours.

For applicable lead or asbestos abatement information, please see the attached notice.

The above information can also be found on the Facilities Disruption section of the University Calendar

For inquiries, please contact:

Name: TOM MINOR **Phone:** 266-4442 **Email:** TMINOR@CLEMSON.EDU

SAMPLE